Target Fixings
Construction Solutions

Using Existing Solid Wall as Part of Pile Cap

8 mm Bar Flex Grouted into existing brickwork and then cast into Concrete.

Cast Concrete

Plan View
Showing way of fixing the reinforcement